

PHONE (605) 225-1212 TOLL FREE 1-888-378-4394

March 15, 2024

Re: West Edge Subdivision Aberdeen, SD Helms A-8668

#### **ADDENDUM NUMBER 1**

The following modifications are made to the plans and specifications for the West Edge Subdivision, Aberdeen, SD.

### **1.)** Contract Documents, Section 00 42 43 – Bid Form. Modifications to Article 6 – Time of Completion. Remove and Replace with the following.

#### **ARTICLE 6 - TIME OF COMPLETION**

Bidder agrees that all dirt work, geotextile separator fabric, geogrid, gravel base course, and curb & gutter and utility work (minus the sanitary sewer lift station and forcemain piping) of Phase 1 will be substantially complete on or before September 6, 2024. Bidder agrees that all utility work of Phase 2 and the sanitary sewer lift station & sewer forcemain piping work will be substantially complete on or before January 31, 2025. Bidder agrees that both lifts of asphalt concrete surfacing shall be substantially complete on Phase 1 by May 16, 2025. Bidder agrees that all remaining work will be substantially complete on or before August 8, 2025; and ready for final payment in accordance with Paragraph 14.07 of the General Conditions on or before August 29, 2025.

## 2.) Contract Documents, Section 00 52 14 – Agreement Between Owner and Contractor for Construction Contract (Unit Price). Modifications to Article 4.02 – Contract Times: Dates. Remove and Replace with the following.

4.02 Contract Times: Dates

A. All dirt work, geotextile separator fabric, geogrid, gravel base course, and curb & gutter and utility work (minus the sanitary sewer lift station and forcemain piping) of Phase 1 will be substantially complete on or before September 6, 2024. All utility work of Phase 2 and the sanitary sewer lift station & sewer forcemain piping work will be substantially complete on or before January 31, 2025. Both lifts of asphalt concrete surfacing shall be substantially complete on Phase 1 by May 16, 2025. All remaining work will be substantially complete on Phase 1 by May 16, 2025. All remaining work will be substantially complete on Phase 1 by May 16, 2025. All remaining work will be substantially complete on or before for final payment in accordance with Paragraph 14.07 of the General Conditions on or before August 29, 2025.

### **3.**) Technical Specification; Section 31 34 20 – Geosynthetic Reinforcement. Revision to Section 1.05.B. Remove and Replace with the following.

- B. The design of the pavement is based on a design traffic loading of <u>315,000 ESALs</u> using the following parameters and based on the asphalt paving section as indicated in the construction plans:
  - i. Subgrade CBR Value: 3.0%
  - ii. Subgrade Modulus: 4,500 psi

### 4.) Technical Specification; Section 33 32 13-13 Sanitary Sewer Duplex Submersible Pump Lift Station. Revisions to Section 2.14. Remove and Replace with the following.

#### 2.14 SPARE PUMPS

A. One spare pump complete with all hardware for installing into wetwell on rail system provided, shall be supplied. The spare pump shall be identical to the ones supplied for the lift station.

#### B. DELETED

### 5.) Technical Specification; Section 33 42 00 Duplex Storm Water Submersible Pump Lift Stations. Revisions to Section 2.10. Remove and Replace with the following.

#### 2.10 SPARE PUMPS

C. One spare pump complete with all hardware for installing into wetwell on rail system provided, shall be supplied. The spare pump shall be identical to the ones supplied for the lift station.


### 6.) Construction Plan Sheets: Sheet 51 of 109. Curb and Gutter Detail Revision. Remove and replace with the attached.

7.) Construction Plan Sheets: Sheet 63 of 109. Construction Phasing Plan Revision. Remove and replace with the attached.

ALL OTHER ITEMS OF THE PLANS AND SPECIFICATIONS REMAIN UNCHANGED.

BY:	ASSOCIATES	
COMPANY NAME:	BY:	
TITLE:	DATE:	

ATTACH THIS SIGNED ADDENDUM NUMBER 1 TO THE BID FORM WHEN SUBMITTING AND/OR ACKNOWLEDGE THE ADDENDUM ON THE BID FORM.



# PHASE 1

### PHASE 2

All dirt work, geotextile separator fabric, geogrid, gravel base course, and curb & gutter, and utility work (minus the sanitary sewer lift station and forcemain piping) of Phase 1 will be substantially complete on or before September 6, 2024.

All utility work of Phase 2 and the sanitary sewer lift station & sewer forcemain piping work will be substantially complete on or before January 31, 2025.

Both lifts of asphalt concrete surfacing shall be substantially complete on Phase 1 by May 16, 2025.

All remaining work will be substantially complete on or before August 8, 2025; and ready for final payment in accordance with Paragraph 14.07 of the General Conditions on or before August 29, 2025.

> CONTRACTOR SHALL HAUL EQUIPMENT AND MATERIAL FROM THE NORTH. THE CONTRACTOR WILL TAKE PRECAUTIONS TO NOT USE OR HAUL ACROSS PAVED SUBDIVISION STREETS.

