

September 25, 2018

Re: Barker Hill Phase II  
A5824

Bid Opening: Wednesday September 26, 2016  
2:00 pm Local Time

## ADDENDUM NUMBER 1

The following modifications are to be made to plans and specifications for the above referenced project.

**1. SECTION 00 21 13 – INSTRUCTION TO BIDDERS - ARTICLE 26, Part 26.03., *add the following paragraph:***

The Contractor is reminded that coordination with the local TERO office is required and their requirements must be met for the Contract to be issued. The Contractor shall note that certain wage rates will apply to this project as required by TERO. The TERO contact is listed below;

DelRay D. German, TERO Director

[DelRayG@swo-nsn.gov](mailto:DelRayG@swo-nsn.gov)

Phone: 605-698-3549

Website: [www.swotero.org](http://www.swotero.org)

PO Box 509

Agency Village, SD 57262

**2. SECTION 00 52 14 – AGREEMENT BETWEEN OWNER AND CONTRACTOR FOR CONSTRUCTION CONTRACT (STIPULATED PRICE), Part 4.02A; *delete and replace with:***

A The work for Bid Schedules A, B & C will be substantially completed on or before **July 1, 2019** and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions on or before **August 1, 2019**.

*Note: No change to Bid Schedule D completion dates.*

**3. SECTION 01 55 26 – TRAFFIC CONTROL, Part 4.02; *delete and replace with:***

**4.02 BASIS OF PAYMENT**

A. Traffic control and all related work specified herein will be incidental to the project and with NO separate payment.

*Note: Bidders are reminded that the traffic control standard plates included in this section are*

*for reference only and all or none may be required to meet the specified requirements as this may depend on Contractor means and methods of construction.*

**4. SECTION 32 10 10 – SCARIFYING AND RECOMPACTING EXISTING WASTEWATER LAGOON SURFACE, Part 3.01.B., delete and replace with:**

B. The Contractor shall remove 6” of existing liner material. Scarify the bottom 6”, compact to specifications, and then re-install the 6” that was removed for the entire width and length of the Cell Floor. The floor shall be flat as indicated on the plans.

**5. SECTION 33 12 13 – WATER SERVICE CONNECTIONS, Part 2.03 C., delete:**

*Note: Corporation stops with a tracer wire nut will not be required.*

**6. SECTION 33 12 19 – WATER UTILITY DISTRIBUTION FIRE HYDRANTS, Part 2.03. P., add:**

Mueller Centurion Fire Hydrants, Model Number A423 are pre-approved to be used on this project.

**PLANS**

1. SHEET 6 GENERAL NOTES, add note:

The Contractor shall be required to install tie bolts per 2015 SD DOT Standard Specifications for Roads and Bridges two standard size pipe back from flared end sections.

2. SHEET 7 ESTIMATE OF QUANTITIES, add note:

The Contractor should note that Site Work and Street Improvement quantities are for reference only and will not be part of this work. The Contractor is also reminded that this project is also Unit Price Bid, and any changes from the as-bid quantities to as-built quantities will be handled according to the General Conditions of the Contract as specified there in.

3. SHEET 11 – BIA HIGHWAY 700 PLAN AND PROFILE SHEET, revise


*All references to the 8 inch watermain remove, dispose and installation along with, fire hydrant reset, tee installation and valve installation was completed by Tribal Forces and this work will not be part of this project. The Contractor will be required to connect to the existing 6” water valve located at Station 501+00, 10’RT on sheet 18.*

4. SHEET 32 – 4<sup>th</sup> STREET PALN VIEW, revise

*All references to the 24 inch RCP Arch pipe shall be replaced with 30” RCP as indicated on the Bid Form.*

ALL OTHER ITEMS OF THE PLANS AND SPECIFICATIONS REMAIN UNCHANGED.

BY: *Leif C. Redinger*  
PROJECT ENGINEER - HELMS AND ASSOCIATES



=====

FIRM NAME: \_\_\_\_\_ BY: \_\_\_\_\_

TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

ATTACH THIS SIGNED ADDENDUM NUMBER 1 TO THE BID FORM WHEN SUBMITTING AND/OR ACKNOWLEDGE THE ADDENDUM ON THE BID FORM.