

September 9, 2020

Re: Partial Air Carrier Ramp
Watertown Regional Airport
Watertown, South Dakota
AIP # 3-46-0058-037-2020
A-7495

Bid Opening: **September 11, 2020**
10:00 am Local Time

ADDENDUM NUMBER 1

The following modifications are made to the plans and specifications for the Partial Air Carrier Ramp, Watertown Regional Airport:

PLANS

- 1. Sheet 8, Plan Notes, Storm Drainage Provisions, delete note in its entirety.**
- 2. Sheet 8, Plan Notes, On-Site Borrow Excavation, revise to read:**

ON-SITE BORROW EXCAVATION

On-Site Borrow Material shall be excavated for this project from the area(s) designated in the plans or as designated by the Owner.

The borrow area(s) shall be stripped of topsoil to a depth of 6 inches and stockpiled. The borrow material shall be excavated as needed, and salvaged topsoil shall be placed and graded as to provide positive drainage. The cost of stripping, stockpiling, and placing topsoil at the borrow area(s) shall be considered incidental work with no measurement or payment being made.

- 3. Sheet 12, Apron Joint Layout and Grading Plan.**

Clarification: The joint details called out carry through the length of the slabs (ALL joints are doweled).

Clarification: Panels adjacent to the Terminal Building (Sta 108+72.5 to Sta 108+90 116' Lt – 8' Lt) may have to be placed via hand work due to the proximity of the Terminal Building walls/footings.

CONTRACT DOCUMENTS AND TECHNICAL SPECIFICATIONS

1. Special Conditions, SC-6 Construction Limitations, Page 19, revise to read:

SC-6. CONSTRUCTION LIMITATIONS.

The Contractor shall comply with the requirements of the Construction Safety Phasing Plan as shown on Sheets 3-7 of the project plans. The Contractor shall have a continuous operation once work begins.

Base Bid:


Excavation and Subbase Course Work may commence in the Fall 2020/Spring 2021

****Base Course work and Concrete Paving shall not commence until after July 1, 2021 unless written authorization from the Owner is received****

The paving of the Air Carrier Ramp shall be completed by August 28, 2021.

The work shall be completed in accordance with Paragraph 50-15 of the General Provisions by September 11, 2021.

ALL OTHER ITEMS OF THE PLANS AND SPECIFICATIONS REMAIN UNCHANGED

BY:  Michael A. Schmit
PROJECT ENGINEER - HELMS & ASSOCIATES

Acknowledge receipt of the Addendum by inserting its number on the Bid Form. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents. It modifies them as above.