


**G.A. APRON RECONSTRUCTION (PHASE 2)
 ABERDEEN REGIONAL AIRPORT
 ABERDEEN, SOUTH DAKOTA
 AIP #3-46-0001-052-2024
 A-9388
 BID TABULATION
 7/16/2024 at 2:00 P.M.**

Base Bid					Reede Construction Inc. Aberdeen, SD		BX Civil & Construction Dell Rapid, SD	
Item #	Spec #	Item Description	Quantity	Unit	Unit Price	Total Price	Unit Price	Total Price
1	C-105	Mobilization	1.0	L.S.	\$320,000.00	\$320,000.00	\$303,393.67	\$303,393.67
2	C-100	Contractor Quality Control Program	1.0	L.S.	\$50,000.00	\$50,000.00	\$53,009.35	\$53,009.35
3	S-100	Construction Safety Phasing Plan	1.0	L.S.	\$155,000.00	\$155,000.00	\$73,000.00	\$73,000.00
4	P-101	Concrete Pavement Removal (6" Nominal Depth)	15,450	SqYd	\$3.50	\$54,075.00	\$10.75	\$166,087.50
5	P-152	Unclassified Excavation	19,913	CuYd	\$5.50	\$109,521.50	\$7.75	\$154,325.75
6	P-152	Disposal of Excess Material	12,744	CuYd	\$3.50	\$44,604.00	\$5.50	\$70,092.00
7	P-154	Subbase Course	10,277	CuYd	\$40.00	\$411,080.00	\$55.00	\$565,235.00
8	P-154	Geogrid	16,085	SqYd	\$2.50	\$40,212.50	\$3.50	\$56,297.50
9	P-154	Geotextile Separator Fabric	16,085	SqYd	\$2.00	\$32,170.00	\$3.00	\$48,255.00
10	P-209	Crushed Aggregate Base Course	2,670	CuYd	\$80.00	\$213,600.00	\$97.00	\$258,990.00
11	P-501	6" Cement Concrete Pavement	479	SqYd	\$110.00	\$52,690.00	\$132.87	\$63,644.73
12	P-501	10" Cement Concrete Pavement	15,538	SqYd	\$110.00	\$1,709,180.00	\$112.95	\$1,755,017.10
13	P-605	Silicone Joint Sealing Filler	14,273	Ft	\$3.00	\$42,819.00	\$2.70	\$38,537.10
14	P-605	Silicone Joint Sealing Filler w/ Expansion Board	1,193	Ft	\$3.00	\$3,579.00	\$2.70	\$3,221.10
15	P-620	Pavement Marking	1.0	L.S.	\$60,000.00	\$60,000.00	\$69,000.00	\$69,000.00
16	F-162	20' Long 10' Chain Link Cantilever Roll Gate	1	Each	\$12,000.00	\$12,000.00	\$20,000.00	\$20,000.00
17	D-701	18" RCP Pipe	416	Ft	\$90.00	\$37,440.00	\$105.00	\$43,680.00
18	D-701	24" RCP Pipe	28	Ft	\$110.00	\$3,080.00	\$140.00	\$3,920.00
19	D-701	Connect to Existing RCP	3	Each	\$1,300.00	\$3,900.00	\$2,150.00	\$6,450.00
20	D-705	6" Perforated Underdrain Piping	1,241	Ft	\$13.00	\$16,133.00	\$30.00	\$37,230.00
21	D-705	Connect Underdrain to Existing Underdrain Piping	6	Each	\$350.00	\$2,100.00	\$1,200.00	\$7,200.00
22	D-751	Underdrain Manhole	3	Each	\$6,000.00	\$18,000.00	\$7,750.00	\$23,250.00
23	D-751	3' x 4' Storm Sewer Inlet w/Type E Frame and Grate	1	Each	\$9,000.00	\$9,000.00	\$21,800.00	\$21,800.00
24	T-901	Seeding and Fertilizing	1,600	SqYd	\$0.50	\$800.00	\$1.50	\$2,400.00
25	T-905	Topsoil (Obtained on Site)	133	CuYd	\$9.00	\$1,197.00	\$12.00	\$1,596.00
26	T-905	Topsoil (Contractor Furnished)	134	CuYd	\$15.00	\$2,010.00	\$34.00	\$4,556.00
27	T-908	Mulching	1,600	SqYd	\$1.00	\$1,600.00	\$2.40	\$3,840.00
28	TL-100	Field Laboratory	1	Each	\$13,000.00	\$13,000.00	\$21,300.00	\$21,300.00
29	Plans	Remove and Dispose of Underdrain Piping	1,241	Ft	\$5.00	\$6,205.00	\$8.50	\$10,548.50
30	Plans	Remove and Dispose of RCP	415	Ft	\$20.00	\$8,300.00	\$24.00	\$9,960.00
31	Plans	Remove and Dispose of Storm Sewer Inlet	1	Each	\$450.00	\$450.00	\$600.00	\$600.00
32	Plans	Remove and Dispose of Underdrain Manhole	3	Each	\$500.00	\$1,500.00	\$1,200.00	\$3,600.00
33	Plans	Adjust Existing Underdrain Manhole Casting	5	Ft	\$600.00	\$3,000.00	\$715.00	\$3,575.00
34	Plans	Remove and Dispose Existing Taxiway Light Can	3	Each	\$1,200.00	\$3,600.00	\$4,100.00	\$12,300.00
35	Plans	Remove and Dispose 10' Chain Link Fence	20	Ft	\$40.00	\$800.00	\$24.00	\$480.00
36	Plans	Aircraft Tie-Downs	11	Set	\$1,100.00	\$12,100.00	\$1,300.00	\$14,300.00
37	Plans	Asphalt Concrete, Composite	217.0	Ton	\$200.00	\$43,400.00	\$213.00	\$46,221.00
38	Plans	Inlet Protection	9	Each	\$120.00	\$1,080.00	\$150.00	\$1,350.00
39	Plans	Clean and Televise Existing Underdrain Pipe	1,050	Ft	\$3.50	\$3,675.00	\$3.75	\$3,937.50
40	01 51 26	Temporary Phasing Work, Electrical	1.0	LS	\$4,000.00	\$4,000.00	\$3,300.00	\$3,300.00
41	26 05 05	Demolition Work, Electrical	1.0	LS	\$350.00	\$350.00	\$370.00	\$370.00
42	L-108	1/C No. 8 AWG, 5 kV, L-824, Type C Cable, Installed in Conduit	884.0	LF	\$2.50	\$2,210.00	\$2.50	\$2,210.00

**G.A. APRON RECONSTRUCTION (PHASE 2)
 ABERDEEN REGIONAL AIRPORT
 ABERDEEN, SOUTH DAKOTA
 AIP #3-46-0001-052-2024
 A-9388
 BID TABULATION
 7/16/2024 at 2:00 P.M.**

Base Bid					Reede Construction Inc. Aberdeen, SD		BX Civil & Construction Dell Rapid, SD	
Item #	Spec #	Item Description	Quantity	Unit	Unit Price	Total Price	Unit Price	Total Price
43	L-108	1/C No. 6 AWG, Solid, Bare Copper Counterpoise Wire, Installed in Trench or Plowed, Including Above Conduit, Ground Rods & Connections/Terminations	508.0	LF	\$4.00	\$2,032.00	\$3.75	\$1,905.00
44	L-110	Remove & Dispose of Existing Conduit & Cable	1.0	LS	\$700.00	\$700.00	\$765.00	\$765.00
45	L-110	Remove & Salvage Existing Cable	1.0	LS	\$150.00	\$150.00	\$160.00	\$160.00
46	L-110	Trenching & Backfilling or Plowing for Conduit	624.0	LF	\$7.00	\$4,368.00	\$7.50	\$4,680.00
47	L-110	Non-Encased, Electrical Conduit, 1-Way, 2-Inch, Type III, Sch. 80 PVC in Trench or SDR 11 HDPE Plowed	512.0	LF	\$8.00	\$4,096.00	\$8.60	\$4,403.20
48	L-110	Non-Encased, Electrical Conduit, 2-Way, 3-Inch, Type III, Sch. 80 PVC in Trench or SDR 11 HDPE Plowed	112.0	LF	\$12.00	\$1,344.00	\$12.50	\$1,400.00
49	L-115	Remove & Salvage for Reinstallation Electrical Manhole	1.0	EA	\$300.00	\$300.00	\$275.00	\$275.00
50	L-115	Reinstall Electrical Manhole	1.0	EA	\$1,000.00	\$1,000.00	\$1,040.00	\$1,040.00
51	L-125	Remove & Salvage for Reinstallation Existing L-861T LED Medium Intensity Taxiway Light, Remove & Dispose of Existing L-867 Base Can & Concrete	8.0	EA	\$150.00	\$1,200.00	\$155.00	\$1,240.00
52	L-125	Remove & Salvage Existing L-853 Taxiway Retroreflective Marker	3.0	EA	\$45.00	\$135.00	\$47.00	\$141.00
53	L-125	Remove & Salvage Existing L-858 Airport Sign, Existing Concrete Site Pad & JB to Remain	3.0	EA	\$250.00	\$750.00	\$270.00	\$810.00
54	L-125	Reinstall L-861T Medium Intensity Taxiway Light on New L-867 Base Can, In Turf	8.0	EA	\$1,500.00	\$12,000.00	\$1,575.00	\$12,600.00
55	L-125	L-861T, 30-Inch Elevated In Turf, Mode 1, LED, Medium Intensity Taxiway Light (MITL) with Heater, Blue, Including Base Can	1.0	EA	\$2,100.00	\$2,100.00	\$2,250.00	\$2,250.00
56	L-125	L-861T, 30-Inch Elevated In Pavement, Mode 1, LED, Medium Intensity Taxiway Light (MITL) with Heater, Blue, Including Base Can	4.0	EA	\$2,800.00	\$11,200.00	\$2,900.00	\$11,600.00
57	L-125	L-858L/Y Location/Direction Lighted Guidance Sign, LED, Size 1, Style 2, Class 2, Mode 2, 3 Module on Existing Concrete Site Pad	2.0	EA	\$3,500.00	\$7,000.00	\$3,700.00	\$7,400.00
58	L-125	L-858Y Direction Lighted Guidance Sign, LED, Size 1, Style 2, Class 2, Mode 2, 3 Module on Existing Concrete Site Pad	1.0	EA	\$3,500.00	\$3,500.00	\$3,500.00	\$3,500.00
59	L-125	Spare Parts	1.0	LS	\$2,900.00	\$2,900.00	\$3,000.00	\$3,000.00
TOTAL BASE BID					\$3,564,236.00		\$4,045,249.00	

I HEREBY CERTIFY THAT THE FOREGOING IS AN ACCURATE REPRESENTATION AND TABULATION OF ALL BIDS RECEIVED AND THAT THE MATHEMATICS HAVE BEEN CHECKED AND ARE TO THE BEST OF MY KNOWLEDGE CORRECT:

PROJECT ENGINEER:  DATE: 7/16/2024